



**ZIMBABWE REVENUE AUTHORITY  
COMMISSIONER GENERAL**

WRITE TO:  
THE COMMISSIONER  
GENERAL  
ZIMBABWE REVENUE  
AUTHORITY  
PO BOX 4360  
HARARE

TELEPHONE:  
+263-4-758891/5  
FAX:  
+263-4-707400  
TELEGRAPHS:  
HARARE

CALL AT:  
RECEPTION  
6<sup>th</sup> FLOOR ZB CENTRE  
CORNER KWAME  
NKRUMAH AVE/ FIRST  
STREET  
HARARE

IN REPLY PLEASE QUOTE:  
NCB23/23

07 August 2023

To All Participating Bidders

**ADDENDUM NO. 1 TO ZIMRA DOMESTIC TENDER NCB23/2023 FOR THE PARTITIONING  
OF ZIMRA KURIMA HOUSE EX BARCLAYS WING.**

Following the compulsory site meeting held on 27 July 2023 at The Zimbabwe Revenue Authority (ZIMRA) offices at Kurima House Ex Barclays Wing, bidders must take note of the following changes:

1. **BILLS OF QUANTITY**

- Bidders must disregard **Annexure A to NCB23/2023** and consider **Annexure A1 to NCB23/2023** for the Bills of Quantity

2. **TENDER CLOSING DATE**

- All bidders must note that the closing date for the Tender NCB23/2023 has been moved from 10 August 2023 to 17 August 2023

**NB: All other requirements will remain unchanged as per Standard Bidding Document**

Thank you

**T. Shonhiwa  
Director, Procurement Management Unit**



ANNEXURE A1 TO NCB 23/2023

**ZIMBABWE REVENUE AUTHORITY**  
**KURIMA GROUND FLOOR (FORMERLY BARCLAYS BANK)**  
**PARTITION WALLS AND FLOOR REFURBISHMENTS**

Item	Description	Unit	Quantity	Rate (\$)	Amount (\$)
	<b><u>Demolitions</u></b>				
	<i>Carefully remove and handover to the client</i>				
1	All existing timber partition walls and doors	Item	1.00		
2	Fitted metal kitchen cabinets	Item	1.00		
	<i>Demolish and carrt-away rubble at contractor's cost</i>				
3	Plastered gypsum partition walls	Item	1.00		
4	Wall tiles, floor tiles, and general rubble	Item	1.00		
	<b><u>Office Partitions</u></b>				
5	Supply and install YALE YK16/YK17 knob-type lockset or equally approved	No.	26.00		
6	Supply and install UNION SN plated CZ80941SR or equally approved indicator bolts	No.	4.00		
7	Supply and install 813 x 2030 internal quality timber door with an approved veneer finish.	No.	30.00		
8	Supply and install a 2.1m high partition wall (1.5m - 12.5mm Rhinoboard and 0.6m to be 0.5mm clear glass complete with beading and the like). Apply an approved vinyl wallpaper and 80mm aluminium skirting on both sides of the wall. Partition wall to be frames using approved aluminium studs and angles.	m	335.00		
9	Supply and install a 3.1m high partition wall (2,4m - 12.5mm Rhinoboard and 0.6m to be 0.5mm clear glass complete with beading and the like). Apply an approved vinyl wallpaper and 80mm aluminium skirting on both sides of the wall. Partition wall to be frames using approved aluminium studs and angles.	m	30.00		
	<b><u>Ablutions and Kitchen Upgrade</u></b>				
10	Supply and install FRANKEE or equally approved signle bowl and signle drainer stainless steel sink including a metal or equally approved vanity cabinet with 30mm black granite tops.	No.	2.00		
11	Supply, install and test wash-hand-basin (WHB) complete with pedestal, two pillar taps per basin, chromium-plated basin waste, angle valves, S-Trap, and other connection materials	No.	4.00		
12	Supply, install and test close couple water closets (WC) complete with the flush master, angle valve, flexible connectors, and pan connector	No.	4.00		



B

13	Supply, install and test "Vaal" or equally approved urinal complete with bottle trap, and angle valves	No.	1.00		
14	Ceramic wall tiling	m2	50.00		-
15	Terazzo floor polishing by a specialist	m2	180.00		-
Sub-Total					-
Add Preliminaries and Generals					-
Sub-Total					-
<u>Add Value Added Tax @ 15%</u>					-
<u>Add Contingencies @ 10%</u>					-
<b>TOTAL</b>					<b>US\$ -</b>



13